



# **REQUEST FOR BID** **RED HILL TRAIL SIGNAGE POST** **FABRICATION, INSTALLATION AND SIGN** **MOUNTING PROJECT**

**OWNER:** Town of Carbondale

**PROJECT:** The fabrication, installation and sign mounting of wayfinding and rules sign posts on the Red Hill Trail System.

**BID DUE DATE:** Bids due by 3:00 p.m. Monday, August 19, 2019

The Town of Carbondale Parks & Recreation Department is seeking bids from construction companies with the skills to fabricate, install and mount wayfinding signs to the sign posts on the Red Hill Trail System. These permanent signs will be mounted and permanently installed in place on various terrain with two different methods and materials, option A is a typical concrete footing, and option B is a footing system needed to install the sign posts in solid rock. Since the cost would fluctuate depending upon what is encountered in each of the different sign locations and the quality of the subsurface material or existing bedrock, the bid should break out the two different mounting options and have a separate but all encompassing price for each mounting method, including time and materials. The Scope of the Project & the Material Specifications that you are bidding out will need to match the following design criteria:

- Company must be bonded and insured.
- Company must be able to provide a Certificate of Insurance with the Town listed as additional insured.
- 7 (Seven) 6' x 6" Cedar posts 5' 6" tall from mounting elevation. (see attached trail node post detail)
- Per post bid per Option A Footing System. Include the post footing attachment system for Option A as it varies per site conditions. Post footings to be black powder coat finished.
- Per post bid per Option B Footing System. Include the post footing attachment system for Option B as it varies per site conditions. Post footings to be black powder coat finished.
- Contractor to set post footing system so post is plumb and vertical.

- Each post must have a Post Cap 6"x 6"x 1" black unlit metal deck post cap with a black finish.
- Sign mounting to post (3/16" thickness signs produced by others that are aluminum signs with adhered 3 M vinyl coating for the graphic content and a UV-protective coating for longevity)
- Signs will have edge of sign aligned flush with post and each post will have various content and sign mounting needs. (See Signage Mount Options 1 & 2)
- Signs and post cap to be mounted with a vandal-proof screw insert a minimum of 1.5" into wood post.
- Install 11 carsonite posts with supplied sticker signage (by others) in locations designated on attached map.
- Ability to conduct the work in the Fall of 2019

Please mail or e-mail the attached completed Bid Sheet to:

Town of Carbondale  
Attn: Eric Brendlinger,  
Parks & Recreation Director  
511 Colorado Avenue  
Carbondale, CO 81623  
ebrendlinger@carbondaleco.net

**TOWN OF CARBONDALE**

**RED HILL TRAIL SIGNAGE POST FABRICATION, INSTALLATION AND  
SIGN MOUNTING PROJECT**

**BID SCHEDULE**

Provide labor, materials, and equipment required for installation of wayfinding and rules sign posts on the Red Hill Trail System that matches the scope and design parameters detailed on the previous page.

Material Descriptions	Quantity	Bid
<b>6"x 6"x 5'6" Cedar post w Post Cap</b>	<b>7 posts</b>	
<b>Trail Node Post Detail: Option A Footing System Installed</b>	<b>Per Post *</b>	
<b>Trail Node Post Detail: Option B Footing System Installed</b>	<b>Per Post*</b>	
<b>Carsonite Posts Installed</b>	<b>11 posts</b>	
<b>Mobilization &amp; Fabrication To cover all costs to complete project as described.</b>	<b>Lump Sum</b>	

**Submitted By:** \_\_\_\_\_  
(Company)

**Submitted By:** \_\_\_\_\_  
(Name/Title of Authorized Bidder)

\_\_\_\_\_  
(Signature)

\_\_\_\_\_  
(contact information- phone & e-mail)

**Date of Bid:** \_\_\_\_\_